HALDIMAND COUNTY DESIGN CRITERIA

SECTION S MINIMUM TESTING REQUIREMENTS

HALDIMAND COUNTY MINIMUM TESTING REQUIREMENTS

Revision Date: Dec. 2000

| MATERIAL | AREA/ USAGE | TEST | SAMPLING FREQUENCY & TEST REQUIREMENTS | TEST LOCATION IDENTIFICATION | |
|-----------------------------------|-------------------------------|----------------------|---|---|--|
| Native Material | Sewer Trench | Compaction | Min. every 15m, .6m max. lift, 95% | Street, distance from downstream M.H., distance above pipe or below final grade ie: Street A, MH23 + 30m, 1.8m above pipe | |
| | Watermain | Compaction | Min. every 15m, .6m max. lift, 95% | Street, station, offset, distance above pipe or below finished grade ie: Street A, 0 + 310, 5.5m Rt, 1m above pipe | |
| | Subgrade | Compaction | Min. every 15m AZ@ pattern 95% 98% desirable in top 1m | Street, Station, offset ie Street A, 0 + 105, 3.5m Lt | |
| | Watermain Road Crossings | Compaction | Each Crossing, 95% | Street, Station | |
| Utility Trenches* C | | Compaction | Each Crossing, 95% | Street, Station | |
| * Utility crossii asphalt | ngs are to be insta | lled prior to base | | | |
| | Service Compaction Trenches** | | Random Selection 25% of lots 95% | Lot Number | |
| ** If Storm and to be reported | <u>-</u> | are installed with I | mainline sewer, this requirement is wa | ived. Only water service trenches will have | |
| Granulars A& | Roadway | Compaction | Min. every 15m AZ@ Pattern 100% | Street, Station, offset ie: Street A, 0 + 105, 3.5m LT | |
| | | Moisture Content | Min. every 15m AZ@ pattern | Street, Station, offset ie: Street A, 0 + 105, 3.5m LT | |

| MATERIAL | AREA/ USAGE | TEST | SAMPLING FREQUENCY & TEST REQUIREMENTS | & TEST LOCATION IDENTIFICATION | |
|----------|--|---|---|---|--|
| | Gradation Percent Crushed PN#(site specific) | - Granulars are to be sampled at source and gradation checked prior to delivery AND - min. 1 check per 100m of road for an 8.5m road - gradation to conform to OPSS Muni 1010 | | | |
| | Utility Trenches | Compaction | Each Crossing 100% | Street, Station | |
| | Curbline Bedding | Compaction | Every 15m | Street, Station Lt or Rt or North, South, East, West | |
| | Driveway | Compaction Contaminatio n | 33% of Driveways at random, 100% - Check to ensure there is 150mm of un-contaminated material | Lot or house #, distance from curb or garage | |

HALDIMAND COUNTY MINIMUM TESTING REQUIREMENTS

| MATERIAL | AREA/ USAGE | TEST | SAMPLING FREQUENCY & TEST REQUIREMENTS | TEST LOCATION IDENTIFICATION |
|--------------------------------------|----------------|--------------------------------|--|--|
| Asphalt HL3 & HL8 1101 1103 | Roadway | Compaction | 15m each lane w/nuclear device 92% HL Mixes as per Table 10 OPSS 310 91% HDBC and Superpave Mixes as per Table 10 OPSS 310 (310.08.06.01) | Street, Station, Lt or Rt or North, South, East, West or adjacent lot ie: Street A, 0 + 225, South lane |
| 1150 | Roadway | Sampling | every 150m each lane (every 100 m on Industrial roads | As Above |
| | Roadway | Asphalt Temperature | every 150m each lane, 120C Min As per PGAC Manufactures Mix Temperature (310.07.06.01, 1150) | As Above |
| | | Ambient Temperature | Each Sample As per OPSS 310.06.02 | |
| | , , | Marshall Tests (1150.07.03) | 2 per day of paving from samples taken | As Above |
| | Roadway | Extraction Tests (1150.07.03) | 2 per day of paving from samples taken | As Above |
| Asphalt HL3,HL3a, HL8 | Driveway | Marshall Tests | 2 per day of paving | Lot or house #, distance from curb or garage |
| | Driveway | Extraction Tests | 2 per day of paving | As Above |

| AREA/ USAGE | TEST | SAMPLING FREQUENCY & TEST REQUIREMENTS | TEST LOCATION IDENTIFICATION |
|-------------------|---|---|---|
| Driveway | Compaction | w/nuclear device 92% HL Mixes as per Table 10 OPSS 310 (310.08.06.01)33% of Driveways at random | As Above |
| Driveway | Temperature | 120C Min As per PGAC Manufactures Mix Temperature (310.07.06.01 | As Above |
| est results are t | o correspond to all OPSS | Standards | |
| ailures, further | testing will be done on th | ne samples to determine the limits of the | |
| ction will depe | nd on nature and extent | | |
| | Driveway Driveway est results are tailures, further | Driveway Compaction Driveway Temperature est results are to correspond to all OPSS ailures, further testing will be done on the | Driveway Compaction w/nuclear device 92% HL Mixes as per Table 10 OPSS 310 (310.08.06.01)33% of Driveways at random Driveway Temperature 120C Min As per PGAC Manufactures Mix Temperature |

| MATERIALS | AREA/ USAGE | TEST | SAMPLING FREQUENCY & TEST REQUIREMENTS | TEST LOCATION IDENTIFICATION | |
|--|--------------------|--------------------------|---|---|--|
| Concrete (OPSS Muni 904) (OPSS Muni 1350) CSA A23.1, CSA | | Compressive Strength | - 3 location per 500m of sidewalk - min 3 cyls. per location for 7 & 28 day breaks | Station, Lt. or Rt. or adjacent lot or house number | |
| A23.2 | | | | | |
| | | Slump | First 3 trucks or until consistent, at sampling & every 3 rd truck | As Above | |
| | | Air Content | First 3 trucks or until consistent, at sampling & every 3 rd truck | As Above | |
| | Curb and Gutter | Compressive Strength | - 3 locations per 500m of Curbing - min. 3 cyls. per location for 7 & 28 day breaks | As Above | |
| | | Slump | First 3 trucks or until consistent, at sampling & every sample location | As Above | |
| | | Air Content CSA A23.1 | First 3 trucks or until consistent, at sampling & every sample location | As Above | |
| | Structures | Compressive Strength | 2 sets (3 samples ea) per pour | As Above | |
| | | Slump | First 3 trucks and every 3 rd truck after and with samples | As Above | |
| | | Air Content | First 3 trucks and every 3 rd truck after and with samples | As Above | |

Notes:

- 1) Additional Testing may be required by the Engineering Manager depending upon site conditions.
- 2) if requested by the Manager of Engineering results of compaction tests for sewer trenches will be plotted on a plan/profile drawing at the site in addition to being submitted to the Engineering Manager in a Tabular Form
- 3) Subgrade will be proof rolled in the presence of the Developers Engineer and Soils Consultant. The Soils Engineer shall issue a certificate of compaction and approval prior to the placement of granular materials, stating that the trenches, services and road subgrade have been backfilled, compacted and tested in accordance with the County's testing criteria and is suitable for the placement of granular materials.
- 4) The Soils Engineer shall issue a certificate of compaction and approval of granular materials prior to the placement of Hot Mix Asphalt.
- 5) All concrete testing shall meet the requirements of CSA A23.1 and CSA A23.2 and applicable Ontario Provincial Standards and Specifications.